INSTALLATION 113
HYDRAULIC LIFTERS
DESCRIPTION 113
REMOVAL 113
CLEANING 114
INSPECTION 114
INSTALLATION 114
PISTON & CONNECTING ROD
DESCRIPTION 115
STANDARD PROCEDURE - PISTON FITTING . 115
REMOVAL 116
INSTALLATION 117
PISTON RINGS
STANDARD PROCEDURE - PISTON RING FITTING 118
VIBRATION DAMPER
REMOVAL 120
INSTALLATION 121
STRUCTURAL SUPPORT
REMOVAL 121
INSTALLATION 121
FRONT MOUNT
REMOVAL 122
INSTALLATION 123
REAR MOUNT
REMOVAL 123
INSTALLATION 124
LUBRICATION
DESCRIPTION 124
OPERATION 124
DIAGNOSIS AND TESTING
DIAGNOSIS AND TESTING - ENGINE OIL PRESSURE 126
DIAGNOSIS AND TESTING - ENGINE OIL LEAK 126
OIL
STANDARD PROCEDURE - ENGINE OIL SERVICE 127
OIL FILTER
REMOVAL 128
INSTALLATION 128
OIL PAN
DESCRIPTION 128
REMOVAL 128
INSTALLATION 129
ENGINE OIL PRESSURE SENSOR
DESCRIPTION 130
OPERATION 130
OIL PUMP
REMOVAL 130
INSTALLATION 130
VALVE TIMING
STANDARD PROCEDURE - VALVE TIMING . . 130
TIMING BELT / CHAIN COVER(S)
REMOVAL 131
INSTALLATION 131
TIMING BELT/CHAIN AND SPROCKETS
REMOVAL 132
INSTALLATION 133
INTAKE MANIFOLD
DESCRIPTION 133
DIAGNOSIS AND TESTING - INTAKE MANIFOLD LEAKAGE 133
REMOVAL 133
INSTALLATION 134
EXHAUST MANIFOLD
DESCRIPTION 134
REMOVAL 135

ENGINE 4.0L

DESCRIPTION

DESCRIPTION - ENGINE BLOCK

The cylinder block is a cast iron inline six cylinder design. The cylinder block is drilled forming galleries for both oil and coolant (Fig. 1).