Verification Tests — Continued

POWERTRAIN VERIFICATION TEST VER - 3	APPLICABILITY
1. NOTE: After completing the Powertrain Verification Test the Transmission Verification Test must be performed. **2. NOTE: If the PCM has been replaced and the correct VIN and mileage have not been programmed, a DTC will set in the ABS Module, Airbag Module and the SKIM.** **3. NOTE: If the vehicle is equipped with a Sentry Key Immobilizer System, Secret Key data must be updated. Refer to the Service Information for the PCM, SKIM and the Transponder (ignition key) for programming information.** 4. Inspect the vehicle to ensure that all components related to the repair are properly installed and connected. 5. With the DRBIII®, clear DTCs. 6. Perform generator output test. Refer to the appropriate service information as necessary. 7. Start the engine and set engine speed to 2000 RPM for at least thirty seconds. 8. Cycle the ignition key off and on. 9. With the DRBIII®, read the DTCs. Are any DTCs or symptoms remaining? Yes → Check for any Technical Service Bulletins and/or refer to the appropriate Symptom list (Diagnostic Procedure). No → Repair is complete.	All