P2503-CHARGING SYSTEM OUTPUT LOW — Continued

TEST	ACTION	APPLICABILITY
2	**WARNING: WHEN THE ENGINE IS OPERATING, DO NOT STAND IN A DIRECT LINE WITH THE FAN. DO NOT PUT YOUR HANDS NEAR THE PULLEYS, BELTS OR FAN. DO NOT WEAR LOOSE CLOTHING.** **NOTE: Ensure all wires are clear of the engine's moving parts.** Start the engine. Warm the engine to operating temperature. Measure the voltage between the Generator B+ Output Terminal and the Battery+ Post. Is the voltage above 0.4 of a volt? Yes → Repair the high resistance in the Battery Positive circuit between the Generator and Battery. Perform POWERTRAIN VERIFICATION TEST VER - 3. No → Go To 3	All
3	**WARNING: WHEN THE ENGINE IS OPERATING, DO NOT STAND IN A DIRECT LINE WITH THE FAN. DO NOT PUT YOUR HANDS NEAR THE PULLEYS, BELTS OR FAN. DO NOT WEAR LOOSE CLOTHING.** **NOTE: Make sure all wires are clear of the engine's moving parts.** Measure the voltage between the Generator Case and Battery ground post. Is the voltage above 0.1 of a volt? Yes → Repair high resistance in the Generator Case Ground. Perform POWERTRAIN VERIFICATION TEST VER - 3. No → Go To 4	All
4	Turn the ignition off. Disconnect the Generator Field harness connector. Using a 12-volt test light, jump it across the Generator Field harness connector. Ignition on, engine not running. With the DRBIII®, actuate the Generator Field Driver circuit. Does the test light illuminate brightly and flash on and off? Yes → Replace the Generator. Perform POWERTRAIN VERIFICATION TEST VER - 3. No → Go To 5	All
5	Turn the ignition off. Using a 12-volt test connected to battery voltage, probe the (Z20) Generator Ground circuit in the Generator Field harness connector. Does the test light illuminate brightly? Yes → Go To 6 No → Repair the open in the (Z20) Generator Ground circuit. Perform POWERTRAIN VERIFICATION TEST VER - 3.	All
6	Disconnect the C3 PCM harness connector. Ignition on, engine not running. Measure the voltage on the (K125) Gen Field Control circuit at the Generator Field harness connector. Is the voltage above 1.0 volt? Yes → Repair the short to voltage in the (K125) Gen Field Control circuit. Perform POWERTRAIN VERIFICATION TEST VER - 3. No → Go To 7	All